

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notification dated 3rd August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Government of Mysore, Bangalore, up to 2 p.m. on 25th August 1933, for "Extending the Power and Lighting Office at Bangalore."

1. The tenders will be opened in public at 2 p.m. on 25th August 1933. The work should be completed within two months; and the monthly progress should not be less than Rs. 1,700.

2. The plan, detailed estimates and the conditions may be seen at the Office of the Chief Electrical Engineer, Bangalore, on all working days during the Office working hours.

3. The tenders should be accompanied by a statement in the form attached, showing the rates at which different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for Extending the Power and Lighting Office at Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender the successful tenderer will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board of the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of notification of acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

12. The contractor should be bound by the conditions of the schedule contract of the Electrical Department.

Statement of quantities for constructing extensions to the Office of the Superintendent,
B. P. L.

Sl. No.	Items of work	Unit	Quantity
1a	Earthwork excavation and filling in basement ...	C.yd.	52
b	Earthwork filling in basement (earth brought from outside):	"	16
2a	Stone jelly concrete foundation ...	C.ft.	457
b	Coursed rubble stone in mortar foundation and basement with bond stones 6' part in every course.	"	1,276
c	Coursed rubble stone in mortar courses to tally with the existing work superstructure.	"	1,268
d	Stone slabs 6" thick exposed part, one line dressed and set in mortar.	S.ft.	169
e	Cut stone arch work ...	C.ft.	17
f	Quoin stones 1" chisel drafted in superstructure ...	"	49
g	Wire-cut brick in mortar for pillars ...	"	90
h	Chunam plastering stone work 2 coats ...	Sqr.	15'00
i	Calcarium distemper washing two coats ...	Sqr.	15'00
j	Dado work as per existing work ...	Rft.	51'00
k	Chunam pointing with thread lines complete ...	Sqr.	16'36
l	White and colour washing two coats ...	"	5'00
3a	Flooring with first class Mangalore tile on 3" concrete and cement pointed complete.	"	5'11
b	Cuddapah slab (1½" thick) flooring on 3" concrete and cement pointed.	"	6'00
4a	Roofing with first class Mangalore tiles with ceiling tiles on teakwood reapers 2" x 1".	"	7'92
b	Roofing with first class Mangalore tiles on teak wood	"	9'20

Sl. No.	Items	Unit	Quantity
5a	Teakwood wrought and put up with two coats of wood oiling complete.	Cft.	72.48
b	Teakwood panelled door with fixtures complete as per existing work.	Sft.	64
c	Teakwood glazed windows with iron bars, etc., complete as per existing work.	"	150
d	Teakwood ventilators glazed fixed complete ...	"	32
e	Teakwood circular ventilators glazed fixed complete ...	"	13
f	Teakwood ornamental eave board as per existing work (12" x 1 1/2").	Rft.	112
g	Teakwood planking 1" thick for valleys fixed complete.	Sft.	28
h	Plain Galvanised iron sheeting for valley fixed complete as per existing work.	"	28
i	Silicate painting three coats (silver grey) ...	Sqr.	15.00
6	Removing and refixing an old window 5' x 7 1/2' into the new masonry.	...	1
7	Steel truss 25 feet clear span fixed complete as per existing work.	Each	1
8	Removing and refixing Mangalore tile roofing with reepers, eave boards, finials, etc., on the gable wall including end rafters.	..	1 Item
9	Removing and refixing Mangalore tile roofing with reepers and eave board, etc., of the verandah roof.	..	1 Item
10	Constructing valley complete as per existing work ...	R.ft.	14
11	Cement border 3" x 3" with Galvd. iron reinforcement at junction of wall and verandah roof.	"	77
12	Chunam patty 6" x 3" at ends of main roof ..	"	38
13	Dismantling the existing pillar and rebuilding the same in the new position using new bricks if necessary and chunam pointed, etc., complete.	..	1 Item
14	Dismantling the existing drain and reconstructing the same using old slabs with chunam concrete and cement plaster.	R.ft.	78
15	Constructing new drain with Cuddapah slab chunam concrete and cement plaster as per existing work.	"	46
16	Putting chunam concrete 3" thick between wall and drain and cement plaster 1/2" thick.	"	124
17	Dismantling steps and removing debris ...	...	1 Item
18	Inserting bond stones 2' x 1 1/2' x 1 1/2' for joining old and new masonry both in foundation and superstructure	Nos.	50
19	Making holes in old wall to insert rafters ...	Each	30
20	Repairs to walls and flooring, etc., of old work after the extension is built.	...	1 Item
21	Burnt brick in clay superstructure ...	Cft.	400
22	Stone slabs 4" thick dressed and set in mortar ...	Sft.	50
23	Chunam plaster 2 coats for brick work ..	Sqr.	12.00

C. M. CARIAPA,
Chief Electrical Engineer.